SINGLE ZONE VAV AIR HANDLING UNITS (AHU-AIR COOLED / AIR SOURCE HEAT PUMP) SCHEDULE *

BASIS OF DESIGN: ANNEXAIR

UNIT NO.	LOCATION	SERVICE	SUPPLY AIR (CFM)	O.A. INTAKE (CFM)	O.A. (%)	RETURN AIR (CFM)	SUPPLY FAN DATA						EXHAUST AIR FAN DATA						TOTAL ENERGY RECOVERY WHEEL DATA																
																				COOLING MODE (SUMMER)						HEATING MODE (WINTER)						APD (IN. WG)		FACE VELOCITY (FPM)	
							QTY	CFM	FAN TOTAL S.P. (IN. W.G.)	E.S.P (IN. WG)	HP/BHP	TYPE/RPM	QTY	TOTAL CFM	FAN TOTAL S.P. (IN. W.G.)	E.S.P. (IN. W.G.)	HP/BHP	TYPE/RPM	SIZE	SUPPLY EAT (DB/WB) °F	SUPPLY LAT (DB/WB) °F	EXHAUST EAT (DB/WB) °F	EXHAUST LAT (DB/WB) °F	TONNAGE TOTAL/SENSIBLE	EFFECTIVENESS (%)	SUPPLY EAT (DB/WB) °F	SUPPLY LAT (DB/WB) °F	EXHAUST EAT (DB/WB) °F	EXHAUST LAT (DB/WB) °F	MBH TOTAL/SENSIBLE	(%)	MOTOR (HP)	SUPPLY	EXHAUST	SUPPLY	EXHAUST
AHU-1	ROOF 2	GYMNASIUM	7200	2300	32%	6150	2	3600	6.99	3.0	11.6 / 10.6	PLUG / 2653	2	3075	3.66	2.0	5.30 / 4.82	PLUG / 2150	02	89 / 73	83.3 / 69.3	78 / 65	87.4 / 71.1	2.76 / 1.17	96	13/11	42.7 / 35.9	72 / 54	87.4 / 71.1	93.98 / 74.17	92.7	0.25	0.68	0.36	657	351
AHU-2	ROOF 2	AUDITORIUM	8500	3550	42%	6750	3	2833	7.10	3.0	7.02/ 6.38	PLUG / 2678	2	3375	3.82	2.0	6.09 / 5.54	PLUG / 1799	03	89 / 73	83.3 / 69.3	78 / 65	87.0 / 70.7	3.50 / 1.15	88	13/11	41.2 / 34.9	72 / 54	22.9 / 22.1	124.14 / 99.28	85	0.25	0.78	0.50	757	485

SINGLE ZONE VAV AIR HANDLING UNITS (AHU-AIR COOLED / AIR SOURCE HEAT PUMP) SCHEDULE CONT. *

BASIS OF DESIGN: ANNEXAIR

UNIT NO.	DX COOLING COIL DATA					DX HEATING COIL DATA				HOT GAS REHEAT COIL				AIR COOLED CONDENSING UNIT			ELECTRIC HEATER			ELECTRICAL DATA								
	CFM	EAT (DB/WB) °F	LAT (DB/WB) °F	TOTAL/SENSIBLE COOLING CAPACITY (MBH)	TONNAGE	CFM	EAT (DB) °F	LAT (DB/WB) °F	TOTAL HEATING CAPACITY (MBH)	CFM	EAT (DB/WB) °F	LAT (DB/WB) °F	CAPACITY (MBH)	TONNAGE	# OF COMP	TYPE OF COMPRESSOR	EAT °F	LAT °F	KW	V/PH/HZ	MCA	MOP	EER/IEER	COP @ 17°F/47°F	REFRI. WT / TYPE	UNIT DIMENSIONS	UNIT WEIGHT TOTAL (LBS)	MODEL NO.	REMARKS
AHU-1	7200	79.7 / 66.17	55 / 55	247 / 197	20.6	6200	59.9	85	169	7200	55	70	119	24	2	VARIABLE SPEED	59.9	85	50	208/3/60	360	400	10.6/16.3	3.44/5.03	43.2 / A 1	368"x93"x90"	10000	ERP-E-07-EW02-HE-D-HR-ASTP	SEE NOTES
AHU-2	8500	80.4 / 66.17	55 / 55	307/ 238	25.6	5355	49.8	85	204	8500	55	70	141	24	2	VARIABLE SPEED	49.8	85	60	208/3/60	425	450	11.2/16.3	3.55/5.43	43.2 / A 1	372"x93"x98"	10200	ERP-E-09-EW03-HE-D-HR-ASTP	SEE NOTES

AHU NOTES:
1. ALL AHU FAN MOTORS SHALL COMPLY WITH THE N.Y.C. ENERGY CODE EFFICIENCIES.
2. PROVIDE SEAMLESS STAINLESS STEEL DRAIN PANS.
3. ERV WHEELS SHALL MEET MINIMUM EFFECTIVNESS OF 75% WHEN IN THEIR "NEW" CONDITION. HEATING AND COOLING COILS TO BE SIZED WITH ERV WHEELS WITH 50% EFFECTIVENESS.
4. AHUS SHALL BE PROVIDED WITH SINGLE POINT POWER CONNECTION WITH UNIT MOUNTED MAIN, SAFETY DISCONNECT SWITCH, CONTROL PANEL, GFI RECEPTACLES AND LAMPS.
5. UNITS SHALL BE PROVIDED WITH 2" MERV-8 PLEATED PRE-FILTER AND 12" MERV-13 PLEATED FINAL FILTER FOR SUPPLY AIR STREAM AND 12" MERV-13 PLEATED PRE-FILTER UPSTREAM OF THE ENERGY WHEEL.
6. ALL AHU FANS (SUPPLY & RETURN) SHALL BE PROVIDED WITH VARIABLE FREQUENCY DRIVE.
7. PROVIDE CONTROLS PER SECTION 15985 AND CONTROL DRAWINGS.
8. ALL SUPPLY AND EXHAUST FANS SHALL BE INTERNALY ISOLATED WITH 2" SPRING DEFLECTION SPRINGS. IN ADDITION, ALL AHUS SHALL BE INSTALLED ATOP OF NEOPRENE ISOLATION PADS WITH MIN. 0.10" STATIC DEFLECTION.
9. ALL FANS SHALL BE AMCA CLASS 1.
10. ACCOUSTICAL PERFORMANCE FOR AIR HANDLING UNITS SHALL BE AS INDICATED IN SPECIFICATION #15934.
11. ALL AHUS SHALL BE PROVIDED WITH SMOKE DETECTORS (ON SUPPLY & RETURN SECTIONS) AND FURNISHED BY ELECTRICAL CONTRACTOR FOR FACTORY INSTALLATION AND WIRING.
12. OVERALL DIMENSIONS DO NOT INCLUDE OA INLET & SPILL AIR HOODS.
13. ALL TOTAL STATIC PRESSURES SHALL INCLUDE DIRTY FILTER (ALL FILTERS) ALLOWANCES.
14. UNIT SHALL BE PROVIDED WITH E-COATING ON INDOOR AND OUTDOOR COILS.
15. UNIT SHALL BE PROVIDED WITH N+1 FAN DESIGN WITH MOTORIZED ISOLATION DAMPERS.
16. UNIT SHALL BE PROVIDED WITH 36" SILENCERS IN SUPPLY AND RETURN AIR PATHS.
17. ALL AHUS SHALL BE PROVIDED WITH ECONIMIZER.

SOUND ATTENUATOR SCHEDULE

BASIS OF DESIGN: IAC

UNIT TAG	SERVICE	SILENCER DIMENSION (W X H X L)	DESIGN CFM	MANUFACTURER AND MODEL	OCTAVE BAND	1	2	3	4	5	6	7	8
					HZ	63	125	250	500	IK	2K	4K	8K
ST-1S, ST-1R	AHU-2 (SA/RA)	36 x 24 x 36	8,500/ 6,750	IAC-3LFL	FACE VELOCITY (1000-2000FPM)	4	8	14-13	20-19	20	15-12	11	10-9

(DOAS) CONSTANT VOLUME AIR HANDLING UNITS FOR CORRIDOR *

TRANE AS STANDARD

UNIT NO.	LOCATION	SERVICE	S.A. CFM	O.A INTAKE CFM	SUPPLY AIR FAN DATA							EXHAUST AIR FAN DATA							TOTAL ENERGY RECOVERY WHEEL DATA							
																				COOLING MODE (SUMMER)				HEATING MODE (WINTER)			
																				SUPPLY		EXHAUST		SUPPLY		EXHAUST	
					QTY	TOTAL CFM	TOTAL S.P IN(INCHES OF W.G)	Ext. SP. IN. WG	BHP	MOTOR (HP)	TYPE / RPM	QTY	TOTAL CFM	TOTAL S.P IN(INCHES OF W.G)	Ext. SP. IN. WG	BHP	MOTOR (HP)	TYPE / RPM	SIZE	E.A.T (DB/WB) °F	L.A.T (DB/WB) °F	E.A.T (DB/WB) °F	L.A.T (DB/WB) °F	COOLING REDUCTION (TON)	E.A.T (DB/WB) °F	L.A.T (DB/WB) °F	E.A.T (DB/WB) °F	L.A.T (DB/WB) °F	HEATING REDUCTION (MBH)
DOAS-1	3RD FLOOR ROOF	CORRIDORS/TOILETS/JC	1950	1950	1	1950	2.28	1.5	1.00	1.5	PLENUM/1942	1	1950	2.29	1.5	1.14	1.5	PLENUM/1714	-	89/73	81.1/67.1	78/64.5	85.9/70.8	3.66	13/10	54.9/43.1	72/54.4	28.8/26.2	115.5

DOAS NOTES:
1. DOAS FAN MOTORS SHALL COMPLY WITH THE N.Y.C. ENERGY CODE EFFICIENCIES.
2. PROVIDE SEAMLESS STAINLESS STEEL DRAIN PANS.
3. ERV WHEELS SHALL MEET MINIMUM EFFECTIVNESS OF 75% WHEN IN THEIR "NEW" CONDITION. HEATING AND COOLING COILS TO BE SIZED WITH ERV WHEELS WITH 50% EFFECTIVENESS.
4. AHUS SHALL BE PROVIDED WITH SINGLE POINT POWER CONNECTION WITH UNIT MOUNTED MAIN, SAFETY DISCONNECT SWITCH, CONTROL PANEL, GFI RECEPTACLES AND LAMPS.
5. UNITS SHALL BE PROVIDED WITH 2" MERV-8 PLEATED PRE-FILTER AND 12" MERV-13 PLEATED FINAL FILTER FOR SUPPLY AIR STREAM AND 12" MERV-13 PLEATED PRE-FILTER UPSTREAM OF THE ENERGY WHEEL.
6. DOAS FANS (SUPPLY & RETURN) SHALL BE PROVIDED WITH VARIABLE FREQUENCY DRIVE.
7. PROVIDE CONTROLS PER SECTION 15985 AND CONTROL DRAWINGS.
8. ALL SUPPLY AND EXHAUST FANS SHALL BE INTERNALY ISOLATED WITH 2" SPRING DEFLECTION SPRINGS. IN ADDITION, ALL AHUS SHALL BE INSTALLED ATOP OF NEOPRENE ISOLATION PADS WITH MIN. 0.10" STATIC DEFLECTION.
9. DOAS FAN SHALL BE AMCA CLASS 1.
10. ACCOUSTICAL PERFORMANCE FOR AIR HANDLING UNITS SHALL BE AS INDICATED IN SPECIFICATION #15939.
11. ALL AHUS SHALL BE PROVIDED WITH SMOKE DETECTORS (ON SUPPLY & RETURN SECTIONS) AND FURNISHED BY ELECTRICAL CONTRACTOR FOR FACTORY INSTALLATION AND WIRING.
12. OVERALL DIMENSIONS DO NOT INCLUDE OA INLET & SPILL AIR HOODS.
13. ALL TOTAL STATIC PRESSURES SHALL INCLUDE DIRTY FILTER (ALL FILTERS) ALLOWANCES.

(DOAS) CONSTANT VOLUME AIR HANDLING UNIT FOR CORRIDOR * CONT.

TRANE AS STANDARD

COOLING COIL DATA										HEATING COIL DATA							ELECTRICAL DATA							
	EAT		LAT																					
CFM	DB (°F)	WB (°F)	DB (°F)	WB (°F)	TOTAL/ SENSIBLE COOLING CAPACITY (MBH)	TONS	ROW/FPI	FACE VOL. (FPM)	EWT/ LWT	FLOW (GPM)	CFM	EAT (°F)	LAT (°F)	TOTAL HEATING CAPACITY (MBH)	ROW/FPI	FACE VOL. (FPM)	EWT/ LWT	FLOW (GPM)	V/PH/HZ	MCA	MOCP	FLA	Unit Dimensions	UNIT WEIGHT TOTAL (LBS)	MODEL NO.	MANUFACTURER	REMARKS
1950	81.1	67.5	52.6	52.5	89.3/62.1	7.4	6/12	122	42/57	12.6	1950	54.9	98.1	91.5	3/10	214	110/120	18.2	208/3/60	14.3	15	13.1	212"x85"x69"	3,272	HORIZON OAD/N REV6-OADG/OANG	TRANE	SEE NOTES

ADITORIUM LOBBY FAN COIL UNIT SCHEDULE *

BASIS OF DESIGN: MAGIC AIR

UNIT NUMBER	SERVICE	SUPPLY AIR (CFM)	RETURN AIR (CFM)	FAN E.S.P (IN. W.G)	FAN T.S.P (IN. W.G)	FAN RPM	FAN BHP/HP	COOLING COIL					HEATING COIL						ELECTRIC DATA			FILTER			MODEL NO.	OPERATING WEIGHT	UNIT SIZE (LxHxW)
								ROW/FPI/TUBE	FACE VOL. (FPM)	TOTAL/SEN. (MBH)	TONNAGE	EDB/ EWB	EWT/ LWT	FLOW (GPM)	ROW/FPI/TUBE	FACE VOL. (FPM)	CAPACITY (MBH)	LDB	EWT/ LWT	FLOW (GPM)	V/PH/HZ	FLA	MCA	TYPE	QTY.	SIZE (HxWxD)			
FCU-C.1	AUDITORIUM LOBBY	1950	1590	1.0	1.62	1144	1.05/1.0	4/10/3/8"	475.2	47.5/38.5	4	80/67	42/57	7	2/10/1/2"	569.5	42.3	74.47	120/102	5	115/1/60	12.8	16	MERV-13	2	20"x20"x2"	HCB16ABAAH2LBACAECCFABAM	347	42"x46"x20"

NOTES:
1. ALL FAN COIL UNIT FAN MOTORS SHALL COMPLY WITH THE N.Y.C. ENERGY CODE EFFICIENCIES.
2. PROVIDE SEAMLESS STAINLESS STEEL DRAIN PANS.
3. PROVIDE CONTROLS PER SECTION 15985 AND CONTROL DRAWINGS.
4. ACCOUSTICAL PERFORMANCE FOR FAN COIL UNITS SHALL BE AS INDICATED IN SPECIFICATION #15838 WITH MAXIMUM NC35.

SERVICE EQUIPMENT PERMITS

CONTRACTOR SHALL FILE FOR AND OBTAIN SERVICE EQUIPMENT PERMITS (ALSO KNOWN AS EQUIPMENT USE PERMITS, CERTIFICATE OF COMPLIANCE) FOR ALL EQUIPMENT NOTED WITH AN ASTERISK (*) IN ACCORDANCE WITH TITLE 28, SECTION BC 105 OF THE NEW YORK CITY BUILDING CODE.

SPLIT-TYPE AC UNITS SCHEDULE (INDOOR EVAPORATOR / OUTDOOR CONDENSING UNIT) *

BASIS OF DESIGN: MITSUBISHI

UNIT NO	SERVICE	TOTAL COOLING CAPACITY MBH	TOTAL HEATING CAPACITY MBH	E.A.T. (COOLING) DB/WB	REFRIG.	INDOOR EVAPORATOR						OUTDOOR CONDENSING UNIT											
						LOCATION	AIR FLOW DRY CFM LO/HI	FAN MOTOR		ELECTRICAL DATA	WEIGHT (LBS)	MODEL NO BASED ON	LOCATION	NO OF COMP.	SOUND LEVEL (dBA)	MCA AMPS	MOCP AMPS	MODEL NO BASED ON	WEIGHT (LBS)	SEER	MIN. SEER BASED ON ECC	MEA NUMBER (SEE NOTE 6)	MANUFACTURER	REMARKS
								MOTOR OUTPUT W	MCA AMPS														
AC-1.1/ ACCU-1.1	1ST FLOOR DATA RM – 101	18	–	75/67	R454B	1ST FLOOR BREAK RM (101)	345/425	30	1.0	208/1/60	30	PKA-A18HA7	ABOVE DOOR	1.0	44	11	28	PUY-A18NHA7	99	18.5	13.0		MITSUBISHI	
AC-2.1/ ACCU-2.1	2ND FLOOR TELEPHONE RM – 225	18	–	75/67	R454B	2ND FLOOR DATA RM (225)	345/425	30	1.0	208/1/60	30	PKA-A18HA7	ABOVE DOOR	1.0	44	11	28	PUY-A18NHA7	99	18.5	13.0		MITSUBISHI	
AC-3.1/ ACCU-3.1	3RD FLOOR MDF RM – 335	18	–	75/67	R454B	3RD FLOOR MDF RM (335)	345/425	30	1.0	208/1/60	30	PKA-A18HA7	ABOVE DOOR	1.0	44	11	28	PUY-A18NHA7	99	18.5	13.0		MITSUBISHI	

NOTES:
1. ALL CONTROL WIRING BETWEEN INDOOR AND OUTDOOR UNITS TO BE PROVIDED BY THE MECHANICAL CONTRACTOR.
2. INDOOR AND OUTDOOR UNIT SHALL HAVE SEPARATE POWER WIRING & DISCONNECT SWITCH. SEE ELECTRICAL DRAWING.
3. ALL AIR CONDITIONING UNITS TO BE PROVIDED WITH WIRED PROGRAMMABLE THERMOSTAT AND LOW AMBIENT CONTROL.
4. ALL UNITS TO BE PROVIDED WITH CONDENSATE PUMPS. REFER TO CONDENSATE PUMP SCHEDULE FOR DETAILS.
5. SEE SPEC. SECTION 15783 FOR DETAILED REQUIREMENTS.
6. IF MEA IS NOT AVAILABLE UNITS MUST BE ETLOR UL–LISTED.
7. UNIT SHALL HAVE THE CAPABILITY TO OPERATE AT 0°F OUTDOOR TEMPERATURE.
8. CONTRACTOR SHALL PROVIDE THE NUMBER OF REFRIGERANT LINES AS REQUIRED TO MATCH THE NUMBER OF COMPRESSOR CIRCUITS IN EACH RESPECTIVE SYSTEM.

SCHEDULE OF CONDENSATE DRAIN PUMPS

BASIS OF DESIGN: BECKETT

UNIT NO.	SERVICE LOCATION	FLOW RATE @ 15' GPH	SHUT OFF FT	ELECTRICAL DATA				MANUFACTURER	MODEL NO.	REMARKS
				WATT	MOTOR H.P.	AMP	VOLT/PH/HZ			
CP–1–1	AC–1–1	33	20	85	1/30	1.5	120/1/60	BECKETT	CB201TUL	SEE NOTE #1
CP–2–1	AC–2–1	33	20	85	1/30	1.5	120/1/60	BECKETT	CB201TUL	SEE NOTE #1
CP–2–2	UV–2–2	33	20	85	1/30	1.5	120/1/60	BECKETT	CB201TUL	SEE NOTE #1
CP–3–1	AC–3–1	33	20	85	1/30	1.5	120/1/60	BECKETT	CB201TUL	SEE NOTE #1

NOTE:
1. ALL CONDENSATE PUMPS SHALL BE INSTALLED OUTSIDE OF THE UNIT, AND CARE SHALL BE TAKEN NOT TO INSTALL THE PUMP DIRECTLY ABOVE ELECTRICAL OUTLET/EQUIPMENT.

EXHAUST FAN SCHEDULE *

"GREENHECK" AS STANARD

UNIT NO.	SERVICE	LOCATION	TOTAL AIR CAP. CFM	EXTERNAL S.P. IN INCHES OF W.G.	MOTOR HP	BHP	MOTOR RPM	TYPE OF FAN	TYPE OF DRIVE	INTERLOCK WITH	DAMPER TYPE	V/PH/HZ	MANUFACTURER	MODEL No	WEIGHT (LBS)	REMARKS
EF–1	LOCKER ROOMS	GYM ROOF	725	0.5	1/4	0.17	1725	CENTRIFUGAL	BELT	SCHEDULED VIA BMS	MOTORIZED	115/1/60	GREENHECK	GB–019–4	60.0	SEE NOTES
EF–2	STORAGES	GYM ROOF	150	0.5	1/6	0.07	1725	CENTRIFUGAL	BELT	SCHEDULED VIA BMS	MOTORIZED	115/1/60	GREENHECK	GB–071–6	57.0	
EF–3	TEACHERS TOILETS	THIRD FLOOR ROOF	300	0.5	1/6	0.16	1725	CENTRIFUGAL	BELT	SCHEDULED VIA BMS	MOTORIZED	115/1/60	GREENHECK	G–081–5	57.0	
EF–4	2ND FLOOR TELEPHONE RM – 225	THIRD FLOOR ROOF	110	0.5	1/6	0.07	1725	CENTRIFUGAL	BELT	SCHEDULED VIA BMS	MOTORIZED	115/1/60	GREENHECK	GB–071–6	57.0	

NOTES:
1. ALL ROOF MOUNTED FANS TO BE PROVIDED WITH 24" HEIGHT PREFABRICATED ROOF CURB AND 12" HIGH EXTENSION CURB WITH GASKETED ACCESS DOOR.
2. ALL FANS SHALL BE PROVIDED WITH DISCONNECT SWITCH.
3. ALL MOTORIZED DAMPERS SHALL MATCH THE MOTOR VOLTAGE OR BE THE TYPE THAT IS CAPABLE OF DIRECT WIRING FROM THE FAN MOTOR NO MATTER WHAT THE VOLTAGE OF THE FAN MOTOR. THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE WIRING OF THIS DAMPER MOTOR FROM THE FAN MOTOR. NO SEPARATE CIRCUIT SHALL BE REQUIRED TO WIRE THE MOTORIZED DAMPER.
4. SEE SPECS FOR ADDITIONAL INFORMATION.
5. ALL THE FAN SHALL SHALL BE OF FAN EFFICIENCY OF 67 MINIMUM.

GRAVITY VENTILATORS SCHEDULE

UNIT NO.	SERVICE	LOCATION	CFM	TYPE / SIZE	EXIST.THROAT SIZE DIAMETER (INCH) V.I.F.	EXISTING ROOF OPENING SIZE WIDTH X LENGTH (INCH)–V.I.F.	DUCT/ DAMPER SIZE (INCHES) V.I.F.	MODEL (AS BASIC OF DESIGN)	WEIGHT (LB)	MANUFACTURER (AS BASIC OF DESIGN)	REMARK
GV–1–1	PROJECTOR CLOSET	GYM ROOF	–	TURBINE GV	8"ø	10x10	–	PT	–	PENNBARRY	

NOTES:
1. GRAVITY VENTILATORS SHALL BE PROVIDED WITH 24" HEIGHT PREFABRICATED ROOF CURB.
2. SEE SPECS FOR ADDITIONAL INFORMATION.

LINEAR DIFFUSER SCHEDULE

BASIS OF DESIGN: ANEMOSTAT

CFM RANGE	INLET SIZE (IN)	THROW (FPM)	CFM/LF	MAX NOISE RATING NC	MODEL	REMARKS
0-300	12"/6"	7	50	20	SLAD	PROVIDED WITH INSULATED PLENUM

WALL MOUNTED RETURN GRILLE SCHEDULE

BASIS OF DESIGN: ANEMOSTAT

CFM RANGE	NOMINAL SIZE (IN)	MAX DUCT VELOCITY (FPM)	CORE AREA (SQ.FT)	MAX NOISE RATING NC	MODEL	LOCATION
0-300	36x36	8.66	350	25	AC-30	GYMNASIUM
301-400	36x36	8.66	350	<20	AC-30	GYMNASIUM/AUDITORIUM
401-600	24x36	5.72	350	<20	AC-30	GYMNASIUM
2500-3300	24x42	500	6.7	<20	30S	AUDITORIUM

ROUND CEILING SUPPLY DIFFUSER SCHEDULE

BASIS OF DESIGN: ANEMOSTAT

CFM RANGE	INLET SIZE (IN)	MAX DUCT VELOCITY (FPM)	THROW (FT)	MAX NOISE RATING NC	MODEL
0-1200	18 Ø	700	20	24	CM-1

CEILING MOUNTED RETURN DIFFUSER SCHEDULE

BASIS OF DESIGN: ANEMOSTAT

CFM RANGE	INLET SIZE (IN)	MAX DUCT VELOCITY (FPM)	THROW (FT)	MAX NOISE RATING NC	MODEL
0-900	16"x16"	550	9-19	<20	3HS

SIDEWALL SUPPLY SCHEDULE

BASIS OF DESIGN: ANEMOSTAT

CFM RANGE	INLET SIZE (IN)	MAX DUCT VELOCITY (FPM)	THROW (FT)	MAX NOISE RATING NC	MODEL
0-100	10"x4"	400	10	<20	10/S
101-300	16"x8"	400	23	<20	10/S
301-400	16"x10"	400	24	<20	10/S

CEILING MOUNTED SUPPLY DIFFUSER SCHEDULE

BASIS OF DESIGN: ANEMOSTAT

CFM RANGE	INLET SIZE (IN)	MAX DUCT VELOCITY (FPM)	THROW (FT)	MAX NOISE RATING NC	MODEL
0-900	18"x18"	400	9-19	25	D

VAV BOX SCHEDULE

BASIS OF DESIGN: ANEMOSTAT

UNIT NO.	SERVICE	INLET (IN.)	AHU #	AIR CFM MAX.	AIR CFM MIN. (OCCUPIED)	AIR CFM MIN. (UN-OCCUP.)	DISCHARGE NC (@1.0 WGSP)	ELECTRIC POWER REQUIRED VOLT/PH/HZ	MODEL NO.	REMARKS
VAV-1.1	GYM INSTRUCTOR RM 130B	6	1	100	100	75	<20	120/1/60	EZTA	SEE NOTES

NOTES:
1. VAV BOX SHALL BE PROVIDED WITH INTEGRAL DISCHARGE SOUND ATTENUTATOR.
2. BOX SHALL BE DIRECT DIGITAL CONTROL (DDC).
3. PROVIDE FACTORY 120/24 VAC TRANSFORMER WITH DISCONNECT SWITCH ON THE SHEET METAL ENCLOSURE FOR EACH VAV BOX.
4. CASING SHALL BE INTERNALLY LINED WITH 1" CLOSED CELL INSULATION.

President & CEO
A. Nina Kubota

Board of Trustees
Chancellor Melissa Aviles Ramos
Peter McCree
Emily A. Youssouf

SCA
NEW YORK CITY
School Construction Authority

Architecture & Engineering
Thierry Poret, FAIA, NCARB, LEED AP, Vice President

Design Consultant Management Studio
Aileen del Prado, P.E. LEED AP BD+C, Senior Director

In–House Design Studio
María A. Gómez, P.E. LEED AP BD+C, Senior Director

Consultants:

NOTE: Drawing may be printed at reduced scale

IT IS A VIOLATION OF THE STATE EDUCATION LAW SECTION 7209 (2) FOR ANY PERSON TO ALTER AN ITEM IN ANY WAY UNLESS SUCH PERSON IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, AND THE ENGINEER STAMPS SUCH CHANGES

No.	Date	Revision

Key Plan:



Block # 5865 Lot # 50

SCA Design Manager:	D. PERSAUD, P.E.
Project Architect/Engineer:	P. DABROWA, P.E
Discipline Lead:	P. DABROWA, P.E.
Designer:	S.THAN
Drawn by:	S. THAN
Checked by:	P. DABROWA, P.E.

Design No or LLW No.:	Building ID:	Date:
D021779	Q169	03/25/2025

Project:
P.S. 169, QUEENS ELECTRIFICATION/ HEAT PUMP SYSTEMS
Address:
18-25 212 STREET, QUEENS, NY 11360

Drawing Title:
HVAC SCHEDULES SHEET #1

DOB NOW Job #
Q00951365-I1

Drawing No.:
M002.00

Sheets in Contract Set: 05 of 44

Sheets in DOB Set: 05 of 44

J:\Design\q\Q169\D021779\Dwgs\m\discipline_set\5-M002.00_Q169.dwg 04/22/25 – 3:51pm 030085